





## An Experienced Team

### The Project Team:

Commercial Services Business Partner Pennaf Housing Group

Development & Technical Manager, Pennaf Housing Group

Contractor

**Employers Agent** 

Architect

Wood Knowledge Wales

Welsh Government

Local Authority, Community Council

Feedback – End user, residents, maintenance, EA.





# Why?

Off-site manufacture reduces construction time on site

Low embodied carbon

Timber is readily available from sustainable source – Europe, UK, Wales?

More Thermally efficient

Higher tolerance on quality due to off site manufacturing

Reduced construction time, Less dependence on good weather

Reduced risk to programme – Speed?

Water tight 2 weeks – from slab up in 2 weeks.

First fix Mechanical & Electrical is more efficient

Insulation fully sustainable

Social conscience.

Engineered solution

Trada guidance available on construction

Reduced risk to overall programme

Less thermal conductivity

Ideal for up to 4 stories

Improved air tightness

Improved u value

Reduced wall thickness overall.

Less wet trades







## Timber Framed Schemes completed:



Ynys Mon, Housing 40No Units in 2010.

Wrexham Housing 10No Units in 2010.









### Timber Framed Schemes completed:



54 Unit Extra Care Scheme Wrexham in 2013.





Colwyn Bay, 50 Bed Residential Care Home 2015.









## Timber Framed Schemes completed:



Adapted Bungalows Welshpool in 2015.



Chirk, Wrexham 66No Bed Residential Care Home 2015.







**Lessons Learnt and Issues:** 

Movement, Cracking, Quality Control of Work, Sprinklers, Fire, Feedback from Residents.

Resolved Movement and Cracking
Resolved Sprinklers
Resolved Fire – Installation and Running of Building (Health and Safety
Executive & North Wales Fire and Rescue.

Residents - Positive ??? Yes





### IS IT ALL A NUMBERS GAME?

Financially – Do these schemes stack up against other forms of construction?
What sets the precedence number of units or sustainability?
Track record? Masonry?
Funding? If Welsh Government funding was not in place would we still be moving in this direction?





Good Cop, Bad Cop?

Am I a sceptic ? Yes!

Contractors and Consultants try to brain wash us with statistics!

End users and clients sell the product – this presently promotes the products!





Supply chain certainty

Contracts – Design & Build versus Traditional Contract

Traditional Insulation v Timber Insulation – performance, cost, availability etc

Welsh Timber?

Timber Insulation? Where from?





Proposed Affordable
Housing Development at
Llanbedr Dyffryn Clwyd, Nr.
Ruthin, Denbighshire





















Low embodied carbon emissions will be ensured by using timber for structure, external joinery and insulation (alternative to petrochemical plastic products).

We have an aspiration subject to funding, viability and ecomomies of scale this housing scheme will not be a one off. We believe that by focusing on whole life costs and whole life carbon, the project team will be able to demonstrate a strong commercial incentive to repeat the approach on multiple schemes throughout Wales. The focus on local timber should act as a stimulus for the forest sector to invest in both planting and in higher value processing creating jobs (particularly in rural areas). This in turn will help Wales meet its legally binding carbon reduction targets in terms of afforestation and carbon storage in timber products in buildings.









### **New Bulld System for Timber Frame Render**




#### System Performance

8 - values 0.26 - 0.10 y - values 0.05 - 0.02

The system complies with the most stringent of standards - from baseline building regulations through to Passivhaus. The system is available in an extensive number of render options including, colour, texture and weathering resistance. All components for the system are available from NBT.

#### Cross-section of system



- 1. NBT 2-cost render system
- 2. NET DEFUTHERM 60/80/100/120mm
- IL Stud fully filled with NBT PAWAFLEX
- 4. Racking board incl. artightness detail (eg OSB 12/15mm) 5. Service yold 25 mm
- (can be insulated for improved performance)
- 6. Plasterboard 12.5 mm
- IZ Plaster, skim and NBT emulsion paint.

#### How NBT systems compare to standard bulld







Matural Bullding Technologies The Hangas Warminghall Road, Oakley, Buckinghamshire HPSE 9UL.

### Components & Accessories for

**NBT System for Timber Frame: Render** 



System build up

















## Delivering Homes & Services

### **Our Growth Plan**

- a) A key contributor to the Welsh Government's target for 20,000 new affordable homes by 2021
- b) Based on a supportive Welsh grant regime
- c) A Development & Investment Strategy which sets out our plans
- d) Aims to deliver 1,500 homes over five years











Grŵp Tai Housing Group



# Recently Completed Projects



Regeneration for rent and sale, Denbighshire







Private Rental, Anglesey



## Recently Completed Projects





Rent to Own, Anglesey

Social Rent - Flintshire





Social Rent - Conwy



Extra Care, Anglesey 63 units, £10m





Extra Care, Flintshire 73 units, £10.2m





Extra Care, Wrexham 60 units, £11m

Social Rent, Wrexham 50 units, £6.5m





